

KEY DATA FOR THE APARTMENT BUILDINGS IN FRANKFURT AM MAIN

Client
Scope of project
Building Class/ Classification (Fire protection)

KEG mbH
Turnkey building including planning
3

Completion
Ready for occupancy

June 2017
4 month including completion of foundation slab

Energy supply
Energy efficiency

Local heating network
Heat protection according to DIN

Gross floor area
Number of houses
Total number of floors
Total number of modules
Total number of apartments
Technical rooms

4.320 m²
8
2
192
40
8

Material walls
Material facades
Material staircases
Material floors

cross-laminated timber
fibre cement boards
stainless steel
cross-laminated timber

Modular construction

Assembly of prefabricated components, delivered just in time, to the field factory line on the building site. Finally, positioning of the modules on the construction site to complete the building.