

# KEY DATA FOR EXTENSION OF PLATENSIEDLUNG

---

Client	ABG Frankfurt Holding
Scope of Project	Turnkey building including Service phases 5-8
Building Class	4

---

Completion of interior fittings	May 2020
Construction time Extension per house	3 months from foundation slab upwards mid. floor

---

Energy supply	City of Frankfurt, District Heating
Energy efficiency	KfW - 55

---

Gross floor area	27.780 m <sup>2</sup>
Number of extended houses	19
Number of floors / house	2
Total number of modules / house	58
Total number of apartments / house	20

---

Material Walls	Cross-laminated timber
Material Fassaden	Wooden frame with Aqua Panel
Material Treppenhaus	Cross-laminated timber
Material Geschossdecken	Cross-laminated timber

---

Modular construction	Assembly of time-controlled delivered precast elements in the production line next to the property. Subsequently, the modules are moved to the finished building on the building site.
----------------------	--