

KEY DATA FOR EXTENSION OF FRITZ-KISSEL-SIEDLUNG IN FRANKFURT AM MAIN

Client	Nassauische Heimstätte Wohnungs- und Entwicklungsgesellschaft mbH
Scope of Project Building Class	Turnkey extension of 14 existing buildings 4 and 5

Completion Construction time	May 2021 3 months from the upper edge of the intermediate floorfloor
---------------------------------	--

Energy supply Energy efficiency	Photovoltaic system KfW 40
------------------------------------	-------------------------------

Number of houses	14
Number of additional floors	1-2
Total Number of modules	301
Number of apartments	82

Material Walls Material Fassaden Material Treppenhaus Material Geschossdecke	Cross-laminated timber Fibre cement boards Cross-laminated timber Cross-laminated timber
---	---

Modular construction	Assembly of prefabricated components, delivered just in time, to the field factory line on the building site. Finally, positioning of the modules on the cons- truction site to complete the building.
----------------------	---